

**TULIP -PRINCETON WATER ASSOCIATION
HWY UTILITY RELOCATION**

BID PROPOSAL

ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
1	400	L.F.	Furnish and Install material, labor and equipment for 4" C-900 PVC Water Main and Fittings including Trench Excavation, Laying, Bedding, Blocking and Backfilling per plans and specifications for the unit price of (INCLUDING PIPE PRICE)	\$ _____	\$ _____
			_____ Dollars and _____ Cents/L.F		
2	200	L.F.	Furnish and Install 4" Type 1 Creek Crossing, including 4" C-906 HDPE Water Main and all necessary fittings, by boring per plans and specifications for the unit price of	\$ _____	\$ _____
			_____ Dollars and _____ Cents/L.F		

BID PROPOSAL CONTINUED

ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
3	4	EA.	Furnish and Install 4" Gate Valve including valve box, valve marker and blocking per plans and specifications for the unit price of	\$ _____	\$ _____
			_____ Dollars and _____ Cents/EA.		
4	4	EA.	Tie in Existing 4" Water Main to Proposed 4" Water Main per plans and specifications for the unit price of (Does not include valve)	\$ _____	\$ _____
			_____ Dollars and _____ Cents/EA.		

BID PROPOSAL CONTINUED

ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
5	1	L.S.	Clear and Grub, as necessary, to allow for proper installation of the proposed water mains. _____ _____ Dollars and Cents/L.S.	\$ _____	\$ _____
6	1	L.S.	Furnish all labor and install all equipment for testing and sterilization of treated mains and appurtenances per plans and specifications for the lump sum price of _____ _____ Dollars and Cents/L.S.	\$ _____	\$ _____

BID PROPOSAL CONTINUED

ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
7	1	L.S.	Contractor shall perform erosion control measures as directed by the engineer and required by the SWPPP for the lump sum price of _____ Dollars and _____ Cents/L.S.	\$ _____	\$ _____
8	1	L.S.	Trench Safety per plans and specifications for the lump sum price of _____ Dollars and _____ Cents/L.S.	\$ _____	\$ _____

BID PROPOSAL CONTINUED

TOTAL OF ALL ITEMS

\$

NOTES

- 1) Miscellaneous items, directed work, connections, etc., not specifically listed but required to complete the proposed improvements to a complete and operational system shall be included in the Bid under the most appropriate Bid Item.
- 2) Time required to complete base bid work shall be 60 calendar days.
- 3) Contractor is to perform and adhere to all requirements of the Storm Water Pollution Prevention Plan found in Exhibit "A" of the Technical Specs.
- 4) Contractor is solely responsible for the complete abandonment of all existing mains unless otherwise noted.

