

McGehee, Arkansas
STREET IMPROVEMENTS PHASE I

BID PROPOSAL

ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
1	1	L.S.	Provide mobilization, preparatory work and operations, including but not limited to, movement of personnel, equipment, supplies, roadway preparation, removal of existing pavement markers, removal of delineators, cleaning of driveway culvert, as required by the plans and specifications for the lump sum price of	\$ _____	\$ _____
			_____ Dollars and _____ Cents/L.S.		
2	1	L.S.	Perform Traffic Control, signage, flaggers, and Barricading to perform the work shown per the plans and specifications for the lump sum price of	\$ _____	\$ _____
			_____ Dollars and _____ Cents/L.S.		

BID PROPOSAL CONTINUED

ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
3	22,705	S.Y.	Perform milling of existing asphalt surface To a depth of 2.5-inches and haul millings to City Yard at McGehee City Hall. This work shall include all equipment, labor, and temporary Traffic controls necessary to complete milling per plans and specifications for the unit price of _____ Dollars and _____ Cents/S.Y.	\$ _____	\$ _____
4	22,705	S.Y.	Provide and Install ACHM Surface Mix (2.5" compacted depth) including prime coat. All labor and equipment as required per the plans and specifications for the unit price of _____ Dollars and _____ Cents/S.Y.	\$ _____	\$ _____

BID PROPOSAL CONTINUED

ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
5	2,500	S.Y.	Furnish and Install Cement and Perform Cement Stabilization (8" Depth) at a rate of 30 lb/sy to existing base to include material, Mixing, equipment, watering, and final compaction Of base per plans and specifications for the unit price of(as required by the engineer)	\$ _____	\$ _____
			_____ Dollars and _____ Cents/S.Y.		
6	2,500	S.Y.	Furnish and Install 10" of class 7 crushed stone including equipment, watering, and final compaction of base per plans and specifications for the unit price of(as required by the engineer)	\$ _____	\$ _____
			_____ Dollars and _____ Cents/S.Y.		

BID PROPOSAL CONTINUED

ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
7	260	S.F.	Furnish all equipment, material, and labor to install 12"-30" Rip Rap drainage (24" Min. Depth) 35 lb. min. on filter fabric including any grading or suitable backfill per the plans and specifications for the unit price of	\$ _____	\$ _____
			_____ Dollars and _____ Cents/S.F.		
8	1	L.S.	Testing Allowance (by Third-Party Laboratory) as Required by the Engineer for soil and material testing per plans and specifications for the lump sum price of (Invoices shall be submitted to be paid)	\$ 5,000	\$ 5,000
			Five Thousand Dollars and zero cents Dollars and _____ Cents/L.S.		
TOTAL BASE BID OF ITEMS 1-8				\$ _____	

NOTES:

1. Submission of the completed Bid Proposal is considered evidence to the Owner that the Contractor fully and clearly understands the complete scope of work and all actions and materials required to complete the work.
2. Items required but not specifically called out in the Bid Proposal shall be included in other items.
3. Time required to complete the base bid work shall be 120 calender days.

