


CITY OF DEQUEEN, ARKANSAS
GROUND STORAGE IMPROVEMENTS
BID OPENING DATE: OCTOBER 18, 2023

ITEM	QTY	UNIT	DESCRIPTION	CUNNINGHAM SANDBLASTING & PAINTING CO.		VIKING PAINTING, LLC		LEHER PAINTING ENTERPRISES, INC.	
				UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE
1	1	L.S.	Blast and Re-coat the full interior of the 72'd x 35' GST	\$	149,550.00	\$	192,000.00	\$	200,000.00
2	1	L.S.	Blast, Re-coat and add the Logo on the full exterior of the 72'd x 35' GST	\$	116,700.00	\$	130,300.00	\$	120,000.00
3	1	L.S.	Furnish and install new roof vent for the GST and #24 stainless steel mesh screen	\$	8,000.00	\$	9,500.00	\$	8,000.00
4	1	L.S.	Furnish and install NSF approved caulk for the interior roof to rim angle connection	\$	500.00	\$	2,100.00	\$	500.00
5	1	L.S.	Furnish and install new interior ladder w/ safety climb device for the Stand Pipe	\$	6,800.00	\$	8,300.00	\$	5,000.00
6	1	L.S.	Furnish and install new sample tap	\$	400.00	\$	2,200.00	\$	1,277.00
7	1	L.S.	Provide full containment for the GST	\$	55,000.00	\$	19,500.00	\$	50,000.00
8	1	L.S.	Provide and install 10" schedule 80 pvc riser pipe, including check valves, bracing, and appurtenance	\$	25,000.00	\$	48,000.00	\$	40,000.00
9	100	L.F.	Additional welding services, used at the direction of the Engineer	\$	4,000.00	\$	4,000.00	\$	5,000.00
10	1	EA	Furnish and install new 30"x30" flanged roof access hatch on the tank	\$	3,000.00	\$	5,500.00	\$	3,500.00
11	1	L.S.	Furnish and install new #24 S.S. wire mesh on all vents and opening	\$	50.00	\$	800.00	\$	500.00
12	1	EA	Furnish and install new 30"D flanged side access hatch on the tank wall	\$	3,000.00	\$	10,500.00	\$	5,500.00
13	1	L.S.	Grade all dirt around tank to drain away from the foundation. Grade shall be 2-4" lower than existing concrete. Clean all dirt and foreign materiil from between tank bottom and concrete, re-caulk seam, and tighten all foundation anchor bolts, prior to blasting and coating	\$	2,000.00	\$	3,700.00	\$	5,000.00
14	1	EA	Furnish and install new water level indicator	\$	4,000.00	\$	5,400.00	\$	3,000.00

CITY OF DEQUEEN, ARKANSAS
GROUND STORAGE IMPROVEMENTS
BID OPENING DATE: OCTOBER 18, 2023

ITEM	QTY	UNIT	DESCRIPTION	CUNNINGHAM SANDBLASTING & PAINTING CO.		VIKING PAINTING, LLC		LEHER PAINTING ENTERPRISES, INC.	
				UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE
15	1	L.S.	Furnish and install all equipment, materials and labor necessary to modify the existing 6" overflow	\$	2,500.00	\$	6,500.00	\$	5,000.00
16	1	L.S.	Furnish and install new confined space entry signage on all manways	\$	200.00	\$	500.00	\$	500.00
17	1	L.S.	Lead abatement and disposal per federal and state regulations	\$	4,000.00	\$	25,000.00	\$	23,000.00
DEDUCTIVE ALTERNATE #1									
1	50	L.F.	Additional welding services, used at the direction of the Engineer	\$	2,000.00	\$	2,000.00	\$	5,000.00
TOTAL OF ITEMS (1-17)				\$	384,700.00	\$	473,800.00	\$	475,777.00
TOTAL OF BASE BID LESS DEDUCTIVE ALTERNATE				\$	382,700.00	\$	471,800.00	\$	470,777.00



[Handwritten Signature]
KIRON BROWNING, P.E., PROJECT ENGINEER

*Note correction made by A.L. Franks Engineering