

ADDENDUM NO. 3

TO: ALL PLAN HOLDERS

RE: COVID Center – Lafayette County, Arkansas

ADDENDUM DATE: May 10, 2022

The Plans, Specifications and Contract Documents for the above referenced project are hereby modified as follows:

1. **Sheet 8: HVAC Units as shown in plans shall be removed and modified to 3-5 Ton heat pumps with electric heat. RHEEM Model RPI160BJ1NA or approved equal. Breaker panel layout shall be adjusted accordingly by electrician to provide power to units meeting all applicable electrical code requirements.**

PROJECT CLARIFICATION

1. Overhead door "D6" shall be chain hoist sectional without windows and shall be insulated.

ADDENDUM NO.3 ISSUED BY:

A.L. FRANKS ENGINEERING



Caleb Mudford, P.E.
Project Manager



5-10-22