



118 East Broad Street  
Texarkana, AR 71854  
PHONE 870.216.1906 • FAX 870.216.1907

## ADDENDUM NO. 1

TO: ALL PLAN HOLDERS

RE: NIX CREEK IMPROVEMENTS– CITY OF TEXARKANA, ARKANSAS

ADDENDUM DATE: May 22, 2025

The Plans, Specifications and Contract Documents for the above referenced project are hereby modified as follows:

### Clarification:

- Time of completion shall be 120 days
- The Scourlok Installation includes only a single basket. Fill within the baskets shall be granular material. The top two inches of fill in the baskets shall be a topsoil, compost, or other approved organic fill to promote vegetation.
- The slope reinforcement shall be the armormax system that includes pyramat 75 and the earth anchor system. Upon compaction and grading of the slope, the slope surface shall include a 2" layer of topsoil, compost, or other approved organic fill to promote vegetation.
- As described by the manufacturer recommendations, a portion of the seed mixture shall be applied prior to sealing the scourlok cell, and prior to installing the armormax slope protection.
- The project will require fill to be placed and compacted at Area B on page 3 of the plans. The fill shall be a High P.I. (greater than 25) soil to restore the bank to the desired slope and plan elevation. This location will require a STAA be completed and work performed from within the channel.
- All other slope stabilization work is proposed to be completed with equipment from the top of bank.

ADDENDUM NO. 1 ISSUED BY:

A.L. FRANKS ENGINEERING

  
\_\_\_\_\_  
Jason Haley, P.E.  
Project Manager

ARKANSAS CERTIFICATE OF AUTHORIZATION NUMBER 1681  
OKLAHOMA CERTIFICATE OF AUTHORIZATION NUMBER 5503  
TEXAS CERTIFICATE OF REGISTRATION NUMBER F-10338