CITY OF MINERAL SPRINGS, ARKANSAS WASTEWATER SYSTEM IMPROVEMENTS

BID PROPOSAL

ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
1	19123	L.F.	Furnish & Install 8" SDR -26 PVC Sanitary Sewer Main, 0-6' deep per plans and specifications for the unit price of	\$	\$
2	12165	L.F.	Furnish & Install 8" SDR-26 PV Savitary Sewer Main, 6-8' deep per plans and specifications for the unit price of	\$	\$
			Dollars and Cents/L.F.		

ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
3	5535	L.F.	Furnish & Install 8" SDR-26 PVC Sanitary Sewer Main, 8-10' deep per plans and specifications for the unit price of	\$	\$
4	2450	L.F.	Furnish & Install 8" SDR-26 FVC sanitary Sewer Main, 10-12' deep per plan and specifications for the unit price of Dollars and Cents/L.F.	\$	\$

ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
5	1031	L.F.	Furnish & Install 8" SDR-26 PVC Sanitary Sewer Main, 12-14' deep per plans and specifications for the unit price of	\$	\$
6	150	L.F.	Furnish & Install 8" SDR-26 Pvc santary Sewer Main, 14-16' deep per plans are specifications for the unit price of Dollars and Cents/L.F.	\$	\$

ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
7	615	L.F.	Furnish & Install 8" Ductile Iron Pipe per plans and specifications for the unit price of	\$	\$
8	650	L.F.	Furnish & Install 10" SDR 25 PVC Santary Sewer Main, 6-8' deep per plans and specifications for the unit price of Dollars and Cents/L.F.	\$	\$

ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
9	450	L.F.	Furnish & Install 10" SDR-26 PVC Sanitary Sewer Main, 0-6' deep per plans and specifications for the unit price of	\$	\$
10	30	L.F.	Furnish & Install 10" Directional Bare per plans and specifications for the unit price of	\$	\$
			Dollars and Cents/L.F.		

ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
11	680	L.F.	Furnish & Install 10" SDR-26 PVC Sanitary Sewer Main, 8-10' deep per plans and specifications for the unit price of	\$	\$
12	200	L.F.	Furnish & Install 10" SDR-26 R) C Sanitary Sewer Main, 10-12' deep per plans are specifications for the unit price of Dollars and	\$	\$
			Cents/L.F.		

ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
13	410	L.F.	Furnish & Install 12" SDR-26 PVC Sanitary Sewer Main, 0-6' deep per plans and specifications for the unit price of	\$	\$
14	550	L.F.	Furnish & Install 12" SDR 25 PVC Santary Sewer Main, 6-8' deep per plans and specifications for the unit price of	\$	\$
			Dollars and Cents/L.F.		

ITEM	QTY	UNIT	DESCRIPTION		UNIT PRICE	TOTAL PRICE
15	150	L.F.	Furnish & Install 12" SDR-26 PVC Sanitary Main, 8-10' deep per plans and specificatio unit price of			
16	1398	L.F.	Furnish & Install 8" Directional Bare per pla specifications for the unit price of	s share and		\$
				sllars and ents/L.F.		\$

ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
17	296	L.F.	Bore & Encase on grade 8" sanitary sewer with 16" X .375" steel encasement per plans and specifications for the unit price of		
			Dollars and Cents I.F.	\$	\$
18	80	L.F.	Bore & Encase on grade 10 sapitary sower with 20" X .375" steel encasement perplais and specifications for the unit price of	\$	\$
			Dollars and Cents/L.F.		

ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
19	204	EA	Furnish & Install Standard 4' Dia. Concrete Manholes per plans and specifications for the unit price of		
			Dollars and Centals A	\$	\$
20	257	V.F.	Furnish & Install Extra Depth Manholes per plans and specifications for the unit price of Dollars and Cents/V.F.	\$	\$

ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
21	150	EA	Abandon existing manholes as necessary for construction in accordance with the plans and specifications for the unit price of	\$	\$
22	2	EA	Tie-in 4" Sewer main to proposed main per plans and specifications for the unit price of	\$	\$
			Cents/EA		

ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
23	9	EA	Tie-in 8" Sewer main to proposed main per plans and specifications for the unit price of	\$	\$
24	212	EA	Reconnect Existing Short Side Service to new main per plans and specifications for the unit price of Dollars and	\$	\$
			Dollars and Cents/EA		

ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
25	164	EA	Reconnect Existing Long Side Service to new main per plans and specifications for the unit price of		\$
26	4160	L.F.	Open Cut and Repair Asphalt Surface ser per plans and specifications for the unit price of	\$	\$

ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
27	1490	L.F.	Open Cut and Repair Concrete Surface per per plans and specifications for the unit price of	\$	\$
28	100	L.F.	Furnish and install aerial crossing for sover main including up to 2 steel pipe supports and concrete encasement on each embanding per plans and specifications for the the unit price of Dollars and	\$	\$
			Cents/L.F.		

ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
29	1000	C.Y.	Provide Gravel Pipe Foundation material for unsuitable subgrade materials (use as directed by the Engineer) per plans and specifications for the unit price of	\$	\$
30	1	L.S.	Provide all equipment and material for resting Sewer Mains and Manholes per plans and specifications for the unit price of	\$	\$
			Dollars and Cents/L.S.		

ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
31	1	L.S.	Provide Trench Safety per Technical Specifications for the unit price of	\$	\$
32	1	L.S.	Furnish and Install All Requirements per Stormwater Pollution Prevention Plan for the unit price of Dollars and Cents/L.S.	\$	\$

ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
33	1	L.S.	Mobilization including preparatory work and operations, including but not limited to, movement of personnel, equipment, supplies, and incidentals to the project site for the lump sum price of		\$
34	1	L.S.	Provide any and all necessary insurance traffic control, inspection, surveying, and other items as required by highway and railroad permits for the lump sum of		\$
			Dollars and Cents/L.S.		
			TOTAL OF ALL ITEMS (1-35)		

ITEM	QTY	UNIT	DEDUCTIVE ALTERNATE #1 DESCRIPTION	UNIT PRICE	TOTAL PRICE
1	296	L.F.	DELETE ITEM #17-Bore & Encase on grade 8" sanitary sewer with 16" X .375" steel encasement per plans and specifications for the unit price of Dollars and Cents/LF.	\$	\$
2	80	L.F.	DELETE ITEM #18-Bore & Encase of grade 10" sanitary sewer with 20" X .375" steel the sement per plans and specifications for the unit price of Dollars and Cents/L.F.	\$	\$

			DEDUCTIVE ALTERNATE #1		
ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
3	296	L.F.	ADD to ITEM # 16-Furnish & Install 8" Directional Bore per plans and specifications for the unit price of	\$	\$
4	80	L.F.	ADD to ITEM # 10-Furnish & toststi 10" Directional Bore per plans and specifications for the unit price of Dollars and Cents/L.F.	\$	\$

TOTAL OF DEDUCT ITEMS (1-4)	\$
TOTAL BASE LESS DEDUCT ITEMS	\$

NOTES

Method to Determine Lowest Bid.

The lowest bid shall be the lowest bid price on the base contract, depending to available funds, without consideration of the prices on the additive or deductive items.

Miscellaneous items, directed work, connections, etc., not specifically is reduced to complete the proposed sewer main line work, and lift station to a complete and operational several be included in the Bid under the most appropriate Bid Item.

- * Contractor is to verify all pipe sizes and flow line elevations of the original manholes.
- * Contractor is to provide Railroad Insurance.