

McGehee, Arkansas
STREET IMPROVEMENTS PHASE I
BID DATE: JUNE 12, 2025
BID TABULATION

ITEM	QTY	UNIT	DESCRIPTION	DIVERSIFIED CONST. & DESIGN	
				UNIT PRICE	TOTAL PRICE
1	1	L.S.	Provide mobilization, preparatory work and operations, including but not limited to, movement of personnel, equipment, supplies, roadway preparation, removal of existing pavement markers, removal of delineators, cleaning of driveway culvert, as required by the plans and specifications for the lump sum price of	\$ 55,000.00	\$ 55,000.00
2	1	L.S.	Perform Traffic Control, signage, flaggers, and Barricading to perform the work shown per the plans and specifications for the lump sum price of	\$ 50,000.00	\$ 50,000.00
3	22705	S.Y.	Perform milling of existing asphalt surface To a depth of 2.5-inches and haul millings to City Yard at McGehee City Hall. This work shall Include all equipment, labor, and temporary Traffic controls necessary to complete milling per plans and specifications for the unit price of	\$ 6.00	\$ 136,230.00
4	22705	S.Y.	Provide and Install ACHM Surface Mix (2.5" compacted depth) including prime coat All labor and equipment as required per the plans and specifications for the unit price of	\$ 26.00	\$ 590,330.00
5	2500	S.Y.	Furnish and Install Cement and Perform Cement Stabilization (8" Depth) at a rate of 30 lb/sy to existing base to include material, Mixing, equipment, watering, and final compaction Of base per plans and specifications for the unit price of(as required by the engineer)	\$ 18.00	\$ 45,000.00
6	2500	S.Y.	Furnish and Install 10" of class 7 crushed stone including equipment, watering, and final compaction of base per plans and specifications for the unit price of(as required by the engineer)	\$ 40.00	\$ 100,000.00
7	260	S.F.	Furnish all equipment, material, and labor to install 12"-30" Rip Rap drainage (24" Min. Depth) 35 lb. min. on filter fabric including any grading or suitable backfill per the plans and specifications for the unit price of	\$ 27.00	\$ 7,020.00
8	1	L.S.	Testing Allowance (by Third-Party Laboratory) as Required by the Engineer for soil and material testing per plans and specifications for the lump sum price of (Invoices shall be submitted to be paid)	\$ 5,000.00	\$ 5,000.00
TOTAL OF ITEMS (1-8)				\$	988,580.00


CODY STRINGER, P.E. PROJECT ENGINEER

