

**CITY OF BEN LOMOND
TANK REHABILITATION
BID DATE: May 17, 2022
BID TABULATION**

ITEM	QTY	UNIT	DESCRIPTION	CUNNINGHAM SANDBLASTING		MAGUIRE IRON		LEHER ENTERPRISES	
				UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE
1	1	L.S.	Blast and Re-coat the full interior of the 50,000 gallon Stand Pipe tank per plans and specifications for the lump sum price of	\$ 31,800.00	\$ 31,800.00	\$ 38,250.00	\$ 38,250.00	\$ 30,000.00	\$ 30,000.00
2	1	L.S.	Blast, Re-coat and add the Logo on the full exterior of the 50,000 gallon Stand Pipe Tank per plans and specifications for the lump sum price of	\$ 37,600.00	\$ 37,600.00	\$ 27,500.00	\$ 27,500.00	\$ 30,000.00	\$ 30,000.00
3	1	L.S.	Furnish and Install new roof vent for the Stand Pipe per plans and Specifications including all labor, materials and #24 stainless steel mesh screen for the lump sum price of	\$ 8,000.00	\$ 8,000.00	\$ 6,500.00	\$ 6,500.00	\$ 7,500.00	\$ 7,500.00
4	1	L.S.	Furnish and install new exterior ladder, including locking ladder gate, for the Stand Pipe for the lump sum price of:	\$ 8,500.00	\$ 8,500.00	\$ 6,500.00	\$ 6,500.00	\$ 10,000.00	\$ 10,000.00
5	1	L.S.	Furnish and install new interior ladder for the Stand Pipe for the lump sum price of:	\$ 6,600.00	\$ 6,600.00	\$ 4,000.00	\$ 4,000.00	\$ 10,000.00	\$ 10,000.00
6	1	L.S.	Furnish and install new sample tap per the plans and specifications for the lump sum price of	\$ 500.00	\$ 500.00	\$ 500.00	\$ 500.00	\$ 1,777.00	\$ 1,777.00
7	1	L.S.	Provide full containment and lead abatement for the 50,000 gallon Stand Pipe For the duration of exterior blasting and painting for the lump sum price of	\$ 47,600.00	\$ 47,600.00	\$ 45,000.00	\$ 45,000.00	\$ 50,000.00	\$ 50,000.00

CITY OF BEN LOMOND
TANK REHABILITATION
BID DATE: May 17, 2022
BID TABULATION

ITEM	QTY	UNIT	DESCRIPTION	CUNNINGHAM SANDBLASTING		MAGUIRE IRON		LEHER ENTERPRISES	
				UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE
8	1	LS	Provide and install 8" schedule 80 pvc riser pipe, including check valves, bracing, and appurtenances per plans and specs for the lump sum price of	\$ 22,500.00	\$ 22,500.00	\$ 24,000.00	\$ 24,000.00	\$ 25,000.00	\$ 25,000.00
9	1	EA	Provide and install overflow modification and concrete splash pad for the 50,000 gallon standpipe, per plans and specs for the unit price of (overflow to be 18-24" above ground level)	\$ 7,000.00	\$ 7,000.00	\$ 8,000.00	\$ 8,000.00	\$ 10,000.00	\$ 10,000.00
10	1	EA	Provide and install new 32" diameter side access hatch per plans and specs for the lump sum price of	\$ 4,000.00	\$ 4,000.00	\$ 9,500.00	\$ 9,500.00	\$ 5,000.00	\$ 5,000.00
11	1	EA	Furnish and Install new 30"x30" flanged roof access hatch on the tank per plans and specifications for the unit price of	\$ 3,500.00	\$ 3,500.00	\$ 6,000.00	\$ 6,000.00	\$ 4,000.00	\$ 4,000.00
12	1	EA	Furnish and Install new water level indicator, including new stainless steel cable, pulleys, float and target on the tank per plans and specifications for the unit price of	\$ 6,000.00	\$ 6,000.00	\$ 5,500.00	\$ 5,500.00	\$ 4,000.00	\$ 4,000.00
13	1	L.S.	Clean/Tighten all foundation bolts on the standpipe per plans and specs for the unit price of	\$ 1,000.00	\$ 1,000.00	\$ 1,500.00	\$ 1,500.00	\$ 1,500.00	\$ 1,500.00
14	100	L.F.	Additional welding services, used at the direction of the Engineer, per plans and specs for the unit price of	\$ 45.00	\$ 4,500.00	\$ 100.00	\$ 10,000.00	\$ 50.00	\$ 5,000.00
TOTAL BASE BID:				\$ 189,100.00	\$ 189,100.00	\$ 192,750.00	\$ 192,750.00	\$ 193,777.00	\$ 193,777.00

CITY OF BEN LOMOND
TANK REHABILITATION
BID DATE: May 17, 2022
BID TABULATION

ITEM	QTY	UNIT	DESCRIPTION	CUNNINGHAM SANDBLASTIING		MAGUIRE IRON		LEHER ENTERPRISES	
				UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE
DEDUCTIVE ALTERNATE No. 1									
15	1	EA	Provide and install new 32" diameter side access hatch per plans and specs for the lump sum price of	\$ 4,000.00	\$ 4,000.00	\$ 9,500.00	\$ 9,500.00	\$ 5,000.00	\$ 5,000.00
TOTAL DEDUCTIVE ALTERNATE 1:				\$ 4,000.00		\$ 9,500.00		\$ 5,000.00	
TOTAL BASE BID LESS DEDUCTIVE ALTERNATE 1:				\$ 185,100.00		\$ 183,250.00		\$ 188,777.00	


KIRON BROWNING, P.E. PROJECT ENGINEER



*Note correction made by A.L. Franks Engineering