

ADDENDUM NO. 1

TO: ALL PLAN HOLDERS

RE: McCURTAIN COUNTY RURAL WATER DISTRICT NO.1
Union Grove Standpipe – Valve Vault Replacement

ADDENDUM DATE: October 30, 2023


The Plans, Specifications and Contract Documents for the above referenced project are hereby modified as follows:

1. Bid Form Revision:

The 6" water main feeding the standpipe needs to have a 6-inch gate valve installed on the main to isolate the standpipe. This is further added by Bid Item #3 in the enclosed revised Bid Form. This scope of work shall be done promptly to allow the system to be opened and returned to pressure in the service area.

ADDENDUM NO. 1 ISSUED BY:

A.L. FRANKS ENGINEERING



Jason C. Haley, P.E.
Project Manager

McCurtain Co. RWD #1

Valve Vault Replacement – Union Grove Standpipe

BASE BID PROPOSAL

<u>ITEM</u>	<u>QTY/UNIT</u>	<u>DESCRIPTION</u>	<u>UNIT PRICE</u>	<u>TOTAL PRICE</u>
1.	1 L.S.	Furnish and Install concrete vault including Aluminum access lid, ladder, piping, valves, Altitude valve, fittings, pipe supports, pressure Gauges, and other components necessary to Complete the valve vault per plans and specifications for the lump sum price of _____ Dollars and _____ Cents/L.S.	\$ _____	\$ _____
2.	1 L.S.	Perform abandonment of existing valve vault To include removal and disposal of existing piping, Vault, placement of fill material, and completion of Pipe connections to new vault per plans and specifications for the lump sum price of _____ Dollars and _____ Cents/L.S.	\$ _____	\$ _____

3. 1 EA Provide and Install 6" Gate Valve to include all Materials, equipment, and labor necessary for The valve installation in accordance with the plans And specification for the unit price of

_____ Dollars and
_____ Cents/EA. \$ _____ \$ _____

TOTAL BASE BID (Items 1-3) \$ _____

Note: A ¾" poly service line (HDPE DR9) shall be installed from the valve vault to within 20-ft of the standpipe as required for pressure reading to the Altitude Valve.

Bid Item #3 placement will be confirmed onsite with the water district. The proposed location is near Highway 3.

