CITY OF LINDEN, TEXAS

JIMS BAYOU WWTP REHABILITATION

BID PROPOSAL

ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
1	1	L.S.	Mobilization of the contractor, as necessary, to provide equipment, labor, and all incidental items, including bonds, insurance, etc., as required to perform the WWTP improvements per the plans and specifications for the lump sup- price of	\$	\$
2	1	L.S.	Remove and dispose of all existing it station equipment including, but not united to, pumps, piping, and all electrical equipment per plans and specifications for the lump sum price of	\$	\$
			Dollars and Cents/L.S.		

ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
3	1	L.S	Furnish and Install new lift station pumps, piping, controls, steel base plate, pump control panel, electrical, valves, labor and all other miscellaneous items for a complete and operational lift station per the plans and specifications for the lump sum price of	\$	\$
4	1	L.S.	Furnish and install equipment and valor necessary to clean out the existing wet well such headworks, and dispose of all Material per plans and specifications for the lump sum price of	\$	\$
			Dollars and Cents/L.S.		

ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
5	1	L.S.	Remove and dispose of the existing baffle curtains and aeration assemblies from the lagoon per plans and specifications for the lump sum price of	\$	\$
6	1	L.S.	Furnish and install new aeration of tuser assemblies (18EA.) per plans and specific trans for the lump sum price of (To include relocation of sludge, as necessary for installation)	\$	\$
			Dollars and Cents/L.S.		

ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
7	1	L.S.	Furnish and install proposed baffle curtains (2 EA.) in the aerated lagoon per plans and specifications for the lump sum price of (To include relocation of sludge, as necessary for installation)		\$
8	1	L.S.	Furnish and install new air ployers (2 5) in the same location as the existing bloyers. To include removal and disposal of existing equipment, and all materials, labor and electrical per plans and specifications for the lump sum price of		\$
			Dollars and Cents/L.S.		

ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
9	1	L.S.	Furnish and install all labor and equipment necessary to Jet/clean the existing 8" force main from the pump station to the aerated lagoon, and furnish and install the pond inlet Modification (2-90's, spool piece and Tideflex valve), and replace the pond outlet valve box per plans and specifications for the lump Sum price of	\$	\$

NOTES: 1) Miscellaneous items, directed work, connections, etc., not specifically listed but required to complete the proposed improvements to a complete and operational system shall be included in the Bid under the most appropriate Bid Item. 2) Any damage to the existing site or equipment caused by proposed work shall be repaired by the contractor per the manufacturer's recommendations at no additional cost to the owner.

3) All fittings, valves and appurtenances must be lead free in accordance with public land 11-380

- 4) Time required to complete work shall be 75 calendar days.
- 5) Contractor shall dispose of all sludge, debris and equipment in accordance with any and a State and federal laws.
- 6) Contractor shall furnish all equipment and materials necessary for this project
- 7) Relocation of sludge, within the lagoon, necessary for equipment installation is the contractor.

BIDDER acknowledges r	receipt of the following KODENDUM:
* Insert "a corporation", "a par Respo	thership", or "an individual" as applicable. actually submitted:
Signature	Address
Title	Date
License Number (If applicable)	License Number (If applicable)
Seal - (if Bid is by Corporation)	Seal - (if Bid is by Corporation) P-7